MYSORE DIVISION.

ADVERTISEMENT.

The 14th February 1889.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 26th February 1889, for constructing masonry tunnels on first 9 miles of Seringapatam, Sosale-Sivasamudram road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1890.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Abstract.

Items.	Per.	Quantity.	Rate.	Amount.
Earthwork excavation	C. Yd.	761		
Stone in concrete	C. Ft.	4,625		
Brick in surki mortar	Do	1,012		
Slab stones	S. Ft.	299		
Do do	C. Ft.	1,123		
Concrete	Do	2,551		
Plastering with surki mortar	Sqr.	14·59		
Gravelling	C. Yd.	854		
Guard stones	Each.	56		
Forming road	L. S.	..		
Do do	R. Yd	155		
Dismantling present structure	L. S.	..		
Brick in morter	C. Ft.	8,969		
Plastering with mortar	Sqr.	66·63		
Earthwork approaches	C. Yd.	5,657		
Baling water	L. S.	..		
Clearing site	Do	..		
Excavation in rock	C. Yd.	65		
Stone in concrete	Do	1,112		
Archwork	C. Ft.	932		
Plastering with mortar	Sq.	24·65		
Iron pipes for draining rain water	Each.	4		
Centering of arches ($\frac{1}{3}$ of archwork)	L. S.	..		
Reforming roadway	R. Yd.	880		
Collecting and carting gravel ($\frac{1}{2}$ mile lead) ..	C. Yd.	636		
Spreading and consolidating gravel	Do	636		

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government promissory notes as earnest money and be superscribed "Tender for constructing a masonry tunnels on first 9 miles of Seringapatam, Sosale-Sivasamudram road, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

V. H. KARVE,
Executive Engineer,